

SECTION 01 56 00 TEMPORARY BARRIERS AND ENCLOSURES

PART 1 - GENERAL

1.1 TEMPORARY FACILITIES

- A. Contractor shall provide and maintain the following temporary facilities as required to complete the Contract:
1. Rubbish chutes, barricades around openings, ladders between floors and similar equipment.
 2. Barricades, lights and similar safety precautions.
 3. All materials and equipment required to safely accomplish Work under this Section shall be in conformance with requirements of California Occupational Safety and Health act (Cal/OSHA), Chapter 5 of CalTrans Traffic Manual and other State and Federal Codes and regulations where applicable.
- B. Removal: Upon completion of the Work, and before the final payment, Contractor shall remove all temporary Work and facilities to put the Project site in the condition required by the General Conditions with no additional cost to the University.

1.2 TEMPORARY PROJECT CONSTRUCTION FENCE

- A. Provide [6 foot high chain link fence type Project barricades] [4 feet by 8 feet plywood fence] [with privacy screening] [without privacy screening] around construction site as required. All construction fencing materials shall be new.
- B. The Contractor is responsible for removal of the fence at the end of construction.
- OR---
- C. The fence will become the property of the University at additional no charge at the end of construction.
- D. Provide gates complete with locking devices.
- E. Use material with smooth surfaces for Work exposed to the public.
- F. Provide fence layout to the University's Representative for approval.
- G. Maintain fence in secure and safe condition to the satisfaction of the University's Representative at all times.
- H. Contractor shall not place any signs, advertisements, notices, or graphic materials on construction fencing that have not been approved in advance by University's Representative.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 56 00