

SECTION 01 54 00 CONSTRUCTION AIDS

PART 1 - GENERAL

1.1 CRANE OPERATION, STAGING AND STORAGE

- A. Operator Training and Crane Certification: Prior to starting crane operations, Contractor shall provide copies of operator's training and crane certification to the University's Representative.
- B. Crane Staging Area: Crane staging areas are shown on Drawings. Contractor will be required to coordinate with the University's Representative a minimum of 5 business days in advance of loading and removal of materials from the roof.
- C. Storage: Contractor will not be allowed on-site crane storage.

1.2 TEMPORARY SCAFFOLDING

- A. Contractor shall provide and maintain the following temporary facilities as required to complete the Contract:
  - 1. Scaffolding, staging, runways, and similar equipment.
  - 2. Hoists or construction elevators, complete with operators, power and signals required.
  - 3. Temporary rigging and similar equipment.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 54 00